



# GAS PERMITS PULLED IN ORANGEBURG COUNTY

## PRESSURE TESTING

**All gas pressure gauges used for testing Residential installations shall be a maximum of 30 P.S.I. when used on the systems stated below.**

1. When testing up to 2 psi gas systems or lower; test pressure applied **must be exactly 5 psi** of air pressure.
2. When testing gas systems 2 psi to 5 psi; test pressure applied **must be exactly 10 psi** of air pressure.

*(Temperature change will be taken into consideration)*

## BONDING OF GAS PIPING

**Gas piping must be electrically bonded by any of the means below.**

1. Bonded to the electrical service grounding electrode system  
*(No Separate grounding rod allowed for bonding purposes)*
2. Appliances that is electrically connected.

**All CSST piping must be bonded back to the electrical service ground electrode system**  
*(No Separate grounding rod allowed for bonding purposes)*

## VISUAL INSPECTION

Any gas piping installed entering the inside of a structure must be inspected for shut off valves. We will require access inside structure to visually inspection gas piping and valves. There will be a \$45 re-inspection fee if structure is locked